



Brockway Carpets Limited
Kidderminster
UK
(01562) 828200
Web: www.brockway.co.uk

ASPEN 50

Total Pile Weight	1695 gms/sq.m	(50 oz/sq. yd)
Tog Rating	1.56	
Construction	Tufted	
Finished Tuft Length	19mm	(3/4 inch)
Pile Height Above Backing	8mm	(0.31 inch)
Pile Fibre Content	80% Pure New Wool, 20% Polypropylene	
Tuft Density	1,575/sq.dcm (101.6/sq.ins.)	
Gauge	31.50/dcm. (8/inch)	
Stitches	50/dcm (12.7/inch)	
Widths	4.00m + 5.00m 13ft 1ins + 16ft 4ins	
Primary Backing:	Woven Polypropylene	
Laminate:	EnviroBac Method (utilising polyolefins)	
*Total Carpet Weight	2289/gms/sq.m.	67.5oz/sq.yd.
*Total Carpet Weight is subject to variation depending on Backing Materials		
Secondary Backing:	Woven Polypropylene	
Recommended Performance:	Extra Heavy Domestic & General Contract	
Colour Fastness:	Light, Shampoo, Dry Rub and Wet Rub to the currently enforced Performance Rating Standards (ISO, EN, BS)	
Mothproofing:	Fully Treated	
Flammability:	LOW - BS4790 Hot Metal Nut	