



Brockway Carpets Limited
Kidderminster
UK
(01562) 828200
Web: www.brockway.co.uk

Shetland

Total Pile Weight	1695 gms/sq.m (50 oz/sq.yd)
Tog Rating	1.56
Construction	Tufted
Finished Tuft Length	20.6mm (13/16 inch)
Pile Height Above Backing	9mm (0.34 inch)
Pile Fibre Content	100% Pure New Wool
Tuft Density	1402/sq.dcm (90.4/sq.ins)
Gauge	31.50/dcm (8/inch)
Stitches	44.5/dcm (11.3/inch)
Widths	4.00m (13ft 1ins)
Primary Backing:	Woven Polypropylene
Secondary Backing:	Woven Polypropylene
Laminate:	EnviroBac Method (utilising polyolefins)
*Total Carpet Weight	2290/gms/sq.m. 67.5oz/sq.yd.
*Total Carpet Weight is subject to variation depending on Backing Materials	
Recommended Performance:	Extra Heavy Domestic & General Contract
Colour Fastness:	All shades are created from natural undyed wools therefore their natural fastness is not altered by the addition of dyestuffs.
Mothproofing:	Fully Treated
Flammability:	B fl - s1 BS EN ISO 13501